




Australian Government

BUILDING AUSTRALIA



Midland Highway Corridor

Infrastructure Investment Program

As at 2025–26 Budget

Total AGC	\$181.3 million
Corridor Description	The Midland Highway between Granton and Launceston
Benefits	<ul style="list-style-type: none">• Improve road safety for all road users• Improve efficiency and network reliability
Funding program	Investment Road and Rail – Infrastructure Investment Program
Transport mode	Road
State	TAS

Projects within the Midland Highway Corridor:

Midland Highway Upgrade - Preconstruction

This project delivered project identification, planning, scoping and development of preconstruction activities to enable the delivery of the final stage of road upgrades for the Midland Highway program.

Midland Highway Safety Works Package - Spring Hill

This project upgraded a 3.4 kilometre section of the Midland Highway at Spring Hill, from Bisdee Tier Road/Tedworth Drive (north) intersection to 2.8 kilometres south of Lower Marshes Road. The improvements included lane, shoulder and verge widening, construction of a centre median with flexible safety barrier and consolidated breaks at intersections, as well as upgrades to roadside drainage, truck stopping bays and the extension of a stock underpass.

Midland Highway Upgrade - Oatlands (Jericho to South of York Plains)

This project delivered road widening, shoulder sealing, additional overtaking lanes and installation of flexible safety barriers on the Midland Highway to improve safety outcomes from Jericho to South of York Plains.

Midland Highway - Campbell Town North (Campbell Town to Epping Forest)

This project includes road widening, shoulder sealing, additional overtaking lanes and installation of flexible safety barriers on the Midland Highway to improve safety outcomes from Campbell Town to Epping Forest. The project will improve the safety on the highway and achieve a minimum 3 Star AusRAP Safety Rating.

Midland Highway Upgrade - Ross (Mona Vale Road to Campbell Town)

This project delivered road widening, shoulder sealing, additional overtaking lanes and installation of flexible safety barriers on the Midland Highway to improve safety outcomes from Mona Vale Road to Campbell Town. The project improved the safety on the highway and will achieve a minimum 3 Star AusRAP Safety Rating once all stages are complete.